

**SAFE WALKS 2015  
DELAWARE, OHIO  
BID NUMBER 01-15**

**ADDENDUM #1**

February 9, 2015

This Addendum shall be attached to and become a part of the bidding documents for Safe Walks 2015, Delaware, Ohio, Bid Number 01-15. Sealed bids will be received by the City of Delaware, Ohio at City Hall, 1 South Sandusky Street, Delaware, Ohio 43015, until 11:00 a.m. EST, on Friday, February 13, 2015 at the Office of the City Manager and opened immediately thereafter. The deadline for inquiries has passed.

**Specifications**

**The price BID shall include the following:**

1. All labor, materials, tools, equipment, and transportation necessary for the proper execution of the WORK in accordance with the CONTRACT DOCUMENTS.
2. All items shall be performed as described in these SPECIFICATIONS in entirety except as herein modified. Work locations are as indicated in the WORK SCHEDULE.
3. The City of Columbus (COC) Construction and Material Specifications (CMS), including all supplements thereto, most recent edition, along with these specifications and the City of Delaware Standard Drawings RDWD-19.1, 19.2, 19.3, 19.4, and 19.5 shall govern all material and workmanship involved in the improvements shown unless otherwise noted.
4. The CONTRACTOR shall have 14-days from removal of any section of walk to have it replaced and open to pedestrian traffic. Residential and commercial driveway areas shall be restored and open to vehicle traffic in no more than 48 hours from start of construction.
5. The CONTRACTOR is responsible to ensure that all walk is left free and clean of all debris including excess concrete and grout material.
6. CONTRACTOR is responsible for protecting all open excavations from pedestrians by use of proper barricades and caution tape around any work area.
7. CONTRACTOR is responsible to trim and remove all tree roots that prevent new walk to be constructed per specification and is considered incidental to Item 608. All roots to be trimmed shall be done with a chain saw or reciprocating saw that can establish clean, vertical cuts. In the event it is determined by the CITY that the amount of tree root trimming required will be detrimental to the health of the tree, the CITY will incur responsibility for tree removal and have stump ground to a minimum of six inches below grade.
8. CONTRACTOR is responsible for protecting all new concrete from vandalism and/or the weather to assure acceptable finish is maintained.
9. It is contractor's responsibility to provide a place for the washout of concrete trucks. Washout may not occur into public storm drains, pavement or tree lawns areas.

10. CONTRACTOR shall restore all disturbed areas to original condition within 7 days from pouring the adjacent sidewalk section(s), unless otherwise noted on the plans. Placement of topsoil, seeding and mulching shall be in accordance with Item 659. The cost for this item shall be incidental to Item 608.
11. The CONTRACTOR is responsible to notify all property owners in writing a minimum of seven (7) days prior to the start of work on sidewalk immediately adjacent to their property. The CITY approve a copy of all written correspondence to the property owners.
12. Upon notification from the CONTRACTOR, property owners shall have two working days to remove any personal property that is in the way of the section of walk to be repaired. The CONTRACTOR shall include this information in the notification to the property owners.
13. CONTRACTOR shall be responsible for posting "No Parking" signs on all streets 72 business hours prior to any operation requiring a ban on parking. Signs shall identify no more than three consecutive days of work and be provided by CONTRACTOR to the satisfaction of the CITY. Signs must be weather resistant meeting City standard, and shall be posted every fifty feet (50') on alternating sides of the street. Signs shall be affixed by heavy-duty staples to 2" wood lathe, four foot (4') long, and not to utility poles, parking meter posts, trees, existing signposts, etc. The cost for this item shall be incidental to Item 608.
14. Contractor shall maintain two-way traffic with appropriate maintenance of traffic operations in accordance with Exhibit TA-10 "Lane Closure on a Two-Lane Road Using Flaggers" at all times. Streets shall remain fully accessible to emergency vehicles, and streets shall be open to vehicular traffic between the hours of 5:00 p.m. and 8:00 a.m., Monday through Saturday and all day Sunday. The Contractor is responsible to keep all commercial driveways open at all times unless otherwise specified on the plans. All such work shall be coordinated with the business owner to minimize disruption (i.e. evening or weekend work may be required).
15. 608, 4", 6" or 8" Concrete Walk, as per plan: All concrete shall have a minimum 28-day compressive strength of 4000 psi. All sidewalks shall have a broom finish aligned perpendicular to the direction travel. Any slabs being replaced adjacent to existing expansion joints shall include the replacement of the expansion joint material per City Standard Drawing RDWD 19.1. All expansion material shall be 1/2" REFLEX rubber expansion joint material or equivalent, conforming to the attached specifications. FOAMTECH concrete expansion joint filler or equivalent shall be used around radii. The installation of all expansion joint material shall be considered incidental to this item. Where new concrete walk ties to existing concrete walk or concrete driveway, the existing concrete shall be removed to the nearest joint and replaced with new concrete as directed by the Engineer. Excavation and material to provide a minimum of 4" of #57 limestone bedding will be considered incidental to this item. Curing compound shall be per 705.07, Type 2 (white opaque) and considered incidental to this item. Use of fly ash is restricted between April 1 and November 1, in addition to restriction between November 1 and April 1 per COC CMS 499.02.
16. 608, 6" Concrete Walk (Class MS), As Per Plan: CONTRACTOR shall place 6" of Class MS (moderate set) Portland Cement Concrete across all residential driveways. CONTRACTOR shall establish full-depth saw cuts to all sidewalk edges prior to removal. Where a clean vertical edge was not maintained after concrete removal, the CONTRACTOR shall saw cut the driveway surface 6" further back from the repair area and replace with similar driveway material at the direction of the ENGINEER. Driveways may be closed a maximum of 48-hours for removal and replacement of walk. Contractor shall give 72-hours advanced notice to the residence owner prior to the closure. Repair of driveway area incidental to Item 608.

17. 608, 8" Concrete Walk (Class MS), As Per Plan: provided for all commercial driveways and at all proposed curb ramps as labeled on the plans.
18. 608, Curb Ramps, As Per Plan (with Detectable Warnings): All curb ramps shall be per City of Delaware Standard Drawings RDWD-19.4 and 19.5
19. 608, Curb Ramps, As Per Plan (without Detectable Warnings): All curb ramps shall be per City of Delaware Standard Drawings RDWD-19.4 and 19.5, excluding the installation of detectable warnings.

**BIDDER SHALL VERIFY RECEIPT OF THIS ADDENDUM ON SHEET BF A1 OF THE BIDDING FORMS.**