

**S. Sandusky St. – Delaware Run Bridge Deck Rehab
DELAWARE, OHIO
BID NUMBER 03-16**

The following specifications shall apply to this project in addition to all plan notes.

Supplemental Specifications

The price BID shall include the following:

1. Pedestrian traffic must be maintained on sidewalks at all times by the use of safety fence around the perimeter of the work zone.
2. The closure shall be extended at the discretion of the ENGINEER, if inclement weather occurs during construction that prevents the minimum cure time as described in ODOT Spec 848.28.
3. The water for this project will be provided at no cost to the contractor from a nearby hydrant. A hydrant meter must be obtained by the CONTRACTOR from the city utility department to monitor the amount of water used. The Utility Department shall be notified by the CONTRACTOR of the scheduled start date to reserve a meter.
4. Upon award, the CONTRACTOR shall provide the CITY with a written schedule of all construction activities to be performed in advance of mobilization of any operation. The following schedule restrictions apply to this project:
 - Work cannot commence until June 4, 2016.
 - All work must be completed within 5 working days of road closure
 - All work must be complete with the road reopened by June 30, 2016
5. Night work and weekend work shall be permitted with advance notice written notice given to the ENGINEER. ENGINEER must approve all night and weekend work.
6. Care shall be taken to minimize dust and prevent waste water run-off.
7. Striping shall be performed by the City Public Works Department upon the curing of the overlay prior to the roadway being reopened.